

WORKS SECTION

Ref: IIAP/PTB/FSD

Date:

INVITATION OF BIDS

ESTABLISHMENT OF PIA OFFICES AT PTB LEVEL-2

ISLAMABAD INTERNATIONAL AIRPORT

1. Pakistan International Airlines intends to construct/furnish different areas allotted to PIA at Aviation building IIAP, Islamabad.
2. Sealed bids are invited from contractors on single stage single envelop bidding procedure.
3. All details can be downloaded from [PPRA](#) website.
4. Pay Order equal to 02% of bid money must be attached with sealed proposal of the bid.
5. Prospective bidders are requested to drop their sealed proposals on or before 18th November 2019, at 10:30hrs, in the office of **Manager Works (FACILITIES MANAGEMENT DIVISION)**, 5th The Mall Booking office Rawalpindi.
6. Tenders will be opened on the same day at 11:00hrs, in the presence of the bidder, who wish to attend.
7. 5% of contract money will be deducted as performance security of the successful bidder and will be released after six months of job completion.

In-Charge Project IIAPs
5TH The Mall PIA booking Office
Saddar Rawalpindis
Pakistan International Airlines
Tel: 051- 9002683
Email: pcbpi@piac.aero

Date:

COMPANY NAME:

CIVIL WORKS

S.NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	12mm thick Glass Partition 5 ft high	700	sft		
2	Glass Door 12 mm including door all accessories i.e floor closer machine, locks , handles etc.	42	sft		
3	12mm thick mineral fiber False Ceiling of 2'x2' size i/c imported T/channel	100	sft		
4	PVC paneling	800	sft		
5	3 coats of paint emulsion/enamel of any color on new surfaces including filling and surface preparation.	800	sft		
6	Frosted sheet	700	sft		
7	0.75"Thick lassani partition	400	sft		
8	Dismantling of existing partition	200	sft		

TOTAL

Electrical works

S/No.	Description of Work	Qty	Unit	Rate	Amount
1	One fan point one light point controlled by one switch, wiring complete with PVC single cable	23	Nos		
2	One three pin socket outlet 15Amps point controlled by one switch ,wiring complete with PVC single core cable 2.5mm in Concealed PVC pipe	4	Nos		
3	Same as above but 5A	16	No		
4	Wiring with PVC cable installed & connected				
5	complete with single core 6mm cable, S/F	25	Mtr		
6	Same as above but 4mm	50	Mtr		
7	Same as above but 2.5mm	300	Mtr		
8	Same as above but 1.5mm	300	Mtr		
9	P/F of rectangular 25mm pvc duct	30	Mtr		
10	PVC conduit 20mm surface	10	Mtr		
11	PVC conduit 25mm surface	20	Mtr		
12	P/F of 3pin Power socket 15	3	No		
13	P/F of 3pin Power socket 5A	3	No		
14	P/F of 3pin Power plug 15	3	No		
15	P/F of MCCB,SP 6 to 63 Amps	8	Nos		

16	P/F of Steel board with provision of multi sockets	6	No		
17	Switch Socket 3Pin flat Multi type	18	Nos		
18	P/F of LED lights ceiling type 21watt Phillips	8	Nos		
19	P/F of ceiling fan 2'x2'	8	Nos		



TOTAL

Air Conditioning

S/No.	Description of Work	Qty	Unit	Rate	Amount
1	P/I of GI sheet duct cover with 1 inch glass wool insulation as per 25SWG standard	560	sqft		
2	P/F of diffuser 2ft x 2ft	2	ea		
3	P/F of grill 2ft x 2ft	2	ea		
4	P/F 2ft x 2ft damper MS	2	ea		
5	Air balancing of diffusers	1	ea		

TOTAL

Furniture

S/No.	Description of Work	Qty	Unit	PICTURE	Rate	Amount
1	Briefing Counters 12 ft long with Granite top able to seat 3 people Top i/c drawers	1	each			
2	Table 4ft with drawers	2	each			
3	Side rack 3ft long	1	each			
4	Low back chairs	5	each			
5	Cabinets 8ft high x 3ft wide x 1.5ft deep	6	each			
6	Looking Mirror 3ft x 6ft incl frame	2	each			
7	Center Table 2ft x 6ft	3	each			
8	Chairs Wooden frame	45	each			
9	Side Table 2ft x2ft	8	each			

TOTAL

Grand Total

For PIA International