

PAKISTAN INTERNATIONAL AIRLINES
FACILITIES MANAGEMENT DIVISION

TENDER NOTICE

Sealed unconditional tenders are invited on single stage single envelope basis from PIA pre-qualified "B & C" Class Civil Contractors.

S.No.	Reference No.	Description of work with location	Tender closing Date & Time	Tender opening Date & Time
1.	DGM (M)/SHIFTING X-RAY/01/2020	Shifting of X-Ray machines & allied Items From Karsaz to PIA Diagnostic Centre at Motor Transport Building Kap.	16-07-2020 14:30 hours	16-07-2020 15:30 hours

Interested parties are requested to collect the tender from the office of the Dy. General Manager (Maintenance) during working hours or tender documents can be downloaded from PIA (www.piac.com.pk).

Tender should be clearly marked with reference no. and name of the work. Tender to be dropped in the "**Tender Box**" placed at Finance Section Facilities Management Division at PIA Head Office, latest by 16-07-2020, and the same will be opened at the specified date & time in presence of interested parties who cares to attend in the office of General Manager (Facilities Management)

PIA reserve the right to accept or reject any or all Tender or scrape the whole tendering process at its own discretion as per PPRA Rules.

Tender should reach not later than given dates & time and the same will be opened at the specified date & times in the office of Dy. General Manager (F.M) , Flight Operation Building, PIA Head Office, Karachi Airport.

For any further query, feel free to contact.

Tel: 021-99043037

Dy. General Manager Maintenance

Works & Projects

PIA Head Office

Pakistan International Airlines

Karachi – Pakistan

Email: rizwan.pasha@piac.aero

PIA-FACILITIES MANAGEMENT DIVISION
MAINTENANCE SECTION
TENDER

To

REF: DGM (M)/SHIFTING X-RAY/01/2020

M/s _____

DATED: _____

DESCRIPTION OF WORK: **Shifting of X-Ray machines & allied Items From Karsaz to PIA Diagnostic Centre at Motor Transport Building Kap.**

S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
01 14/34	Supply and fix, Gypsum Ceiling 600mm x 600mm x 7.5mm thick, incl Aluminum Tee & Aluminum angle, 25mm x 25mm x 1mm, incl hanger clips, jointing clips and 14 SWG, GL wire etc, complete.	53.54	Sqm	991.44	53071.78
02 12/101	Same as item 12-100, but Textured.	53.54	Sqm	958.85	51336.83
03 06/60	Supply and fix 19mm thick Chip board veneered both sides of specified pattern in any position commercial.	35	Sqm	723.36	25317.60
04 06/52	Supply & fix, Formica, 0.8mm thick.	5.20	Sqm	397.03	2064.56
	<u>NON-SCHEDULE</u>				
01	Supply/Fix Lead Sheet on Wall/Doors as per Directives Incharge (for Stop Radiation)	252	Sft	L/S	
02	Shifting of X-ray Machines (03 Nos) The following jobs are required. 1. Dismantling carefully the existing X-Ray Machines 2. Packing and loading of X-Ray Machines and allied equipment's with manual and mechanical equipment and transportation to new site 3. Carefully offloading and placing X-Ray Machines at required place 4. Servicing Cleaning and connecting of equipment for operational use 5. Finally commissioning and handing over the X-Ray Machines to PIA Radiologist	01	Job	L/S	
	Total:-				

1. PIA reserves the right to accept or reject your Tender without assigning any reason.
2. You are required to deposit Rs. **2%** As Earnest Money with the Cashier and obtain receipt or in form of Pay order. The receipt should be attached with this form.
3. Tender will be opened on 16-07-2020 at 15:30 Hrs. by Tendering Committee in the presence of contractors who care to attend.
4. Period required for completion **15 Days**.

FOR PAKISTAN INTERNATIONAL AIRLINE

SEAL & SIGNATURES
OF THE CONTRACTOR