

Ref: PEW/FMD/CIVIL/2020/26

Date: November 05, 2020

## **TENDER NOTICE**

### **REPLACEMENT OF SEWER LINE & SEPTIC TANK AT PIA BOOKING OFFICE PESHAWAR**

Sealed unconditional bids are invited from all B / C class enlisted Civil Contractors for the above noted work. Bids should be addressed and reach to Works Officer (Civil) PIA, PIA Booking Office, 33-The Mall, Arbab Road, Peshawar Cantt. by November 23, 2020 till 10:30 hrs and will be opened on the same day at 11:00 hrs in the Office of the District Manager KP, PIA Booking Office, 33-The Mall, Arbab Road, Peshawar Cantt. Bids shall accompany 2% earnest money (refundable) in the form of pay order in favour of PIA.

On the face of the envelope reference PEW/FMD/CIVIL/2020/26 must be written.

Works Officer (Civil),  
PIA Booking Office Peshawar,  
33-The Mall, Arbab Road, Peshawar Cantt.  
Tel: 091-9212370-79 Ext: 249

**TENDER FORM**

M/S \_\_\_\_\_  
\_\_\_\_\_

Ref: PEW/FMD/CIVIL/2020/26  
Date: November 05, 2020

**DESCRIPTION OF WORK: REPLACEMENT OF SEWER LINE & SEPTIC TANK AT PIA BOOKING OFFICE  
PESHAWAR**

Please send not later than 23-11-2020 (10:30 hrs) your sealed unconditional bids for the work mentioned herein as per following terms and conditions:

1. PIA reserves the right to accept or reject any bids without assigning any reason.
2. Bids shall accompany **2% earnest money (refundable)** of the bid amount in the form of pay order in favour of PIA.
3. Bids will be opened on 23-11-2020 at 11:00 hrs in the office of the District Manager KP, in the presence of the contractors who wish to attend.
4. Bids should remain valid for **Three Months**.
5. Period required for the completion of the work is **45 Days**.
6. All works will be approved by the Engineer on duty.
7. PIA reserves the right to cancel the work order at any stage of the work without assigning any reason as per PPRA Rules-2004 para no. 33.
8. PIA accepts only standard materials strictly in accordance with the specifications. Any inferior or substandard materials, if used, shall be rejected out-right hand and registration of the contractor concerned may be cancelled.
9. PIA shall have the option to increase or decrease the quantity of any item mentioned in the quotation / work order.
10. The contractor to whom the contract is awarded shall have to abide by the rules and regulations mentioned in the work order as well as the rules and regulations of PIA.
11. No excuse of non-availability of materials and / or fluctuation in the market rates etc. shall be accepted.
12. If the work is delayed after given time period, Rs. 500/- per day will be deducted, up to maximum 10% of the total bid value.

Seal & Signature of the contractor

For: **Pakistan International Airlines**

## TENDER FORM

M/S \_\_\_\_\_  
\_\_\_\_\_

Ref: PEW/FMD/CIVIL/2020/26  
Date: November 05, 2020

### REPLACEMENT OF SEWER LINE & SEPTIC TANK AT PIA BOOKING OFFICE PESHAWAR

S.No	Description Of Items	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
<b>RCC Sewer &amp; Manholes:</b>					
1	Carefully taking up or down, glazed or encaustic tiling to floors, hearths or walls i/c borders, skirting moldings, capping etc and CM setting, but not backing.	30.58	Sqm		
2	Dismantling un-reinforced lime or CC and premix carpet etc.	7.39	Cum		
3	Excavation as in Hard Soil upto 1.5m depth, in foundation and pipe trenches and independent holes upto 30 sqm and throw earth clear of edges of excavation within 10m.	47.14	Cum		
4	P/L sand cushion in bed.	10.62	Cum		
5	Manholes, complete, ractangular or circular as described, exc 600 mm deep but not exc 1800 mm deep with iron steps, 230 mm thick brick walls, complete in all respect.	2.04	Cum		
6	P/L RCC Type B manhole cover, complete with angle iron frame embeded in concrete, complete in all respect.	2	Each		
7	S/F RCC pipes 375 mm bore, laid and jointed with spigot socket or tongue and groove joint, i/c rubber ring complete in all respect.	36.57	Meter		

Seal & Signature of the contractor

For: **Pakistan International Airlines**

8	P/L CC 1:4:8 using crushed or broken stone graded as specified in bed and encasing of pipe.	24.21	Cum		
9	Back filling as in ordinary or hard soil, in pipe trenches, 1.5 M below Ground Level, with spoil obtained from excavation in trenches, i/c watering and compaction in 150mm layer and dressing to required profile and shape.	37.71	Cum		
10	P/L CC 1:2:4 using crushed or broken stone graded as specified in flooring and roadway.	7.39	Cum		
11	Laying mosaic tiles, 300 mm x 300 mm (excluding rate of tiles but including cleaning of the available used tiles) complete in all respect.	30.58	Sqm		
12	Disposing of dismantled unsuitable / surplus material away from PIA premises.	7.39	Cum		
<b>Septic Tank:</b>					
1	Dismantling un-reinforced lime or CC and premix carpet etc.	1.55	Cum		
2	Excavation as in Hard Soil exceeding 1.5m depth, in foundation and pipe trenches and independent holes upto 30 sqm and throw earth clear of edges of excavation within 10m.	32.23	Cum		
3	P/L CC 1:2:4 using crushed or broken stone graded as specified in bed of septic tank, complete in all respect.	0.65	Cum		
4	Burnt Brick work, in wall 115 mm thick, laid and jointed in CM 1:3, straight or to curve, upto 4.25 m depth.	0.72	Cum		
5	Burnt Brick work, in wall over 115 mm thick, laid and jointed in CM 1:3, straight or to curve, upto 4.25 m depth.	1.57	Cum		

Seal &amp; Signature of the contractor

 For: **Pakistan International Airlines**

6	Burnt Brick work (excluding rate of bricks but including cleaning of available used bricks), in wall over 115 mm thick, laid and jointed in CM 1:3, straight or to curve, upto 4.25 m depth.	2.83	Cum		
7	13mm thick cement plaster 1:3, using puddlo or similar material @ 3% by weight of cement, finished as specified.	44.24	Sqm		
8	P/L pre-cast RCC slab, length 1.52 m, width 0.457m, weight 79.10 Kg, i/c hoisting, setting & jointing in CM 1:4, all as specified.	4.18	Sqm		
9	Back filling as in ordinary or hard soil, in pipe trenches, building etc., 3.5 M below Ground Level, with spoil obtained from excavation in trenches, i/c watering and compaction in 150mm layer and dressing to required profile and shape.	7.67	Cum		
10	P/L sand cushion in bed.	1.55	Cum		
				<b>Total =</b>	

- Rates must be inclusive of all taxes.
- All contractors are advised (not mandatory) to visit site prior to submitting bids / tenders.

Seal & Signature of the contractor

For: **Pakistan International Airlines**