

MGR/W-L/E-CARGO/2019  
8<sup>TH</sup> January 2020

**TENDER NOTICE**

**CLOSING OF EXISTING FENCING UPTO ROOF IN EXPORT WARE HOUSE AT PIA CARGO  
COMPLEX LAHORE.**

Seal un-conditional tenders are invited from all B class enlisted civil contractors for the above subject work. Tender should be addressed to General Manager Facilities Management Division and dropped in tender box placed in account section works by 23<sup>TH</sup> January 2020 till 15:00 hrs and will be open on the same day at 15:30 hrs in the office of General Manager Facilities Management. All details regarding the tender can be downloaded from [www.piac.com.pk](http://www.piac.com.pk). 2 % Earnest money of the bid should be attached with the tender.

On the face of envelop reference must be written MGR/W-L/E-CARGO/2019.

**GENERAL MANAGER (FACILITIES MANAGEMENT DIVISION)**

Pakistan International Airline.  
1<sup>ST</sup> FLOOR, FLIGHT OPERATION BUILDING  
PIA HEAD OFFICE.  
Tel: 021-99044650  
Email: [gmfacmgmt@piac.aero](mailto:gmfacmgmt@piac.aero)

**CLOSING OF EXISTING FANCING UPTO ROOF IN EXPORT WARE HOUSE AT PIA  
CARGO COMPLEX LAHORE.**

S No.	Sch. No.	Description	Qty.	Unit	Rate	Amount
1	C-SA-09-85	Same as item 09-82, but 18 BG.	151.14	Sqm		
2	C-SA-09-22	Supply and fix, guard bars, grills railings ladders brackets, hooks hold fasts and frames etc cut to dead length, reduced tp size, shape, figure etc, incl. punching/drilling holes if necessary and fixing, assembling by welding or with the use of bolts, nuts, rivets washers etc. and erection / fixing in position incl. making good the disturbed surface.	1,470.00	Kgs		
3	C-SA-09-89	Supply and fix pipes of black sheets 18 BG any Dia, welded or riveted side joints (fixed length to nearest 15mm)	66.65	Sqm		
4	C-SA-15-58	1st Coat of painting on new or old work such as steel doors, windows and CSWs of any type and description with synthetic enamel paint.	302.28	Sqm		
5	C-SA-15-59	Same as item 15-58, but 2nd and subsequent coat.	302.28	Sqm		
6	C-SA-15-59	Same as item 15-58, but 2nd and subsequent coat.	302.28	Sqm		
7	C-SA-09-116	Supply and fix, wire netting, iron galvanized 25mm x25mm mesh 14 SWG and fixed with tinned tacks, G.I staples etc, as required	276.84	Sqm		
<b>TOTAL AMOUNT RS.</b>						



**DRAWING**

**PLAN FOR CLOSING OF EXISTING FANCYING UPTO ROOF IN  
EXPORT WARE HOUSE AT PIA CARGO COMPLEX LAHORE.**

